

RIG ABAN IV

Rig Type	Jack up
Design & Class	Baker Marine 300-IC; Independent Leg Cantilever;MODU ABS A1
Construction & Conversion Year	Promet Private Ltd., Singapore, 1983 Major Upgrade Nov1999
Flag	Panama
Water Depth	300'
Drilling Depth	21,000'
Quarters	96 Persons
Hull	212' X210' X 26'
Variable Load	5456 Kips
Heliport	70' Dia
Storage	Mud & Cmt Bulk-9,000 cu.ft; Liquid Mud-2,000bbls; Fuel-5,600 bbls; Drill Water-4,577bbls; Pot Water-1,830 bbls
Drilling Equipment	Drawworks-Ideco 2100E;Driven by two Jeumont Schneider DC Motors. Mud Pumps-2 Ideco T1600, Triplex,1,600 hp Driven by 2 GE 752 DC Motors each. Prime movers-Four CAT3516B,1,850 HP each; SCR System TPC AC-SCR; Rotary Table-Ideco 37 1/2", Independent motor driven Top Drive-Canrig 1050 E2SP,1,130 hp, 500 T
Derrick	Joseph Paris ; 147' x 30' x 30' 1,392,000 lbs.
BOP System	One Double 13-5/8" x 10M Cameron - Type U Ram Preventer One Single 13-5/8" x 10M Cameron - Type U Ram Preventer One 13 5/8", Cameron 5,000 psi Annular Preventer; One 21 1/4",Cameron 2,000 psi,D Annular Preventer; 37 1/2" Regan Model- KFDJ-500 Diverter.
Cranes	Two BMC-900; 25T @ 20'
Mooring	Four 10,000 lbs Baldt Moorfast Anchors; Four Electric motor driven winches; 50,000 lbs pull each
Positioning	Nil
Work Area	Bombay High, India
Former Names	Hitdrill-I
Nett Registered Tonnage	1968
IMO Number	8751693

